

# **Commissioning Cable System for Key Account Customer**

Danielle Anderson – APS UG Engineer

Ronald Roberts – APS UG Engineer



# Introduction


- Arizona Public Service (APS) serves approximately 1.4 million customers
- Our service territory stretches across the state, from the southern border of Mexico all the way up to the Grand Canyon






# The Challenge

- Had three (3) splice failures within the span of 6 months on feeders that serve key account customer with sensitive loads
- Lost customer's confidence in our ability to provide reliable power



# The Challenge


- **1<sup>st</sup> Splice Failure - 12/9/2022**
  - Original install year 2021
  - Feeder loading 1.5MW
- **2<sup>nd</sup> Splice Failure – 5/2/2023**
  - Original install year 2022
  - Feeder loading 0.9MW
- **3<sup>rd</sup> Splice Failure – 5/22/2023**
  - Original install year 2022
  - Feeder loading 0MW





# The Challenge

- Multiple feeders in manhole
- For safety reasons, all feeders in manholes were de-energized to make splice repairs causing major impacts to our customer



# Action Taken

- Laid out temporary cable to bypass permanent feeders to eliminate risk of another splice failing unexpectedly
- Committed to our customer that we would remove and re-install all their permanent feeders
- Committed to our customer that we would eliminate as many splices as possible during re-install





# Action Taken

- Sent faulted splices and a select few non-faulted splices out for evaluation
- Performed Partial Discharge (PD) commissioning testing on all newly installed feeders
- PD testing distribution feeders has not been an APS practice
- Performing this additional test showed our commitment to ensure the reliability of all newly installed feeders





# PD Testing Results

- Installation crews were required to rebuild multiple terminations due to PD detection found at 1.0 U<sub>o</sub> and 1.5 U<sub>o</sub>
- PD Testing found some subpar termination installs
- PD Testing forced installation crews to slow down and be super meticulous at critical steps during installs




### CABLE SYSTEM COMMISSIONING SUMMARY

	Circuit Segments	Mitigations
<b>SUBSTATION A</b>	<b>21</b>	<b>33</b>
Feeder 04	5	22
Feeder 05	4	5
Feeder 14	3	0
Feeder 15	3	2
Feeder 24	3	0
Feeder 25	3	4
<b>SUBSTATION B</b>	<b>8</b>	<b>1</b>
Feeder 03	4	0
Feeder 13	4	1(Splice)
<b>TOTAL</b>	<b>29</b>	<b>34</b>

**34 Mitigations**  
 33-Terminations  
 1-Splice

## PD Testing Results

11 of 29 [38%] of New Segments Did Not Meet Standard




### Pre-Mitigation

● Meets Standards ● Substandard

# PD Testing Results

## MITIGATION METHODS

- Decontamination
- Corrected Cutback
- Corrected Stress Control Position
- Mechanical Void Compression
- Reapplied Void Filler (Mastic)
- Replaced Termination



**Post-Mitigation**

● Meets Standards ● Meets Standards Mitigated





# Splice Root Cause Analysis - Summary

- 4 samples received of 15kV Class [ ] Cold Shrink Shear Bolt Joints installed on [ ] Cu 1000kcmil EPR 220 mil Flat Strap Concentric Wire cable.
- 1 sample had faulted in service. The other 3 samples had not been PD tested in the field.
- The observations listed below would most likely exhibit substandard performance and shorten the design life of the joint.

Sample ID	Observations
Joint Sample 1	<ul style="list-style-type: none"> <li>• Root cause of faulted joint was determined to be a dimensional error. The dimensions used to make the semi-con cutbacks were too long, causing the overall cable dimension within the splice body to be too long. This caused the stress control within the splice body to be misaligned over the cable.</li> </ul>
Joint Sample 2	<ul style="list-style-type: none"> <li>• Both semi-con cutbacks were not radial. Discharge control compound (Blue Grease) was scarce along cable insulation.</li> <li>• Splice body was not centered over entire joint.</li> </ul>
Joint Sample 3	<ul style="list-style-type: none"> <li>• Right side semi-con cutback was not radial.</li> </ul>
Joint Sample 4	<ul style="list-style-type: none"> <li>• Both semi-con cutbacks were not radial. The dimensions used to make the semi-con cutbacks were too long, causing the overall cable dimension within the splice body to be too long.</li> <li>• Splice body was not centered over entire joint. This, combined with dimensional error, caused the stress control within the splice body to be misaligned over the cable.</li> </ul>

## DIMENSIONS



DIMENSION CUTBACK TO CUTBACK = 20 ½"  
SPECIFICATION - NOT BE GREATER THAN 19 ¾"



DIMENSION CUTBACK TO CUTBACK = 20 ½"  
SPECIFICATION - NOT BE GREATER THAN 19 ¾"

## CUT-BACKS



SEMI-CON CUTBACK IS NON-RADIAL




IMPROPER CUTBACKS

## VOID FILLER | DCC




BLUE DISCHARGE CONTROL COMPOUND (DCC)  
SCARCE ALONG INSULATION

## INTERFACE | ALIGNMENT



SPLICE BODY NOT OVERLAPPING SEMI-CON;  
INSULATION IS VISIBLE



SPLICE BODY MISALIGNED –STRESS CONTROL MUST OVERLAP SEMI-CON



SPLICE BODY NOT OVERLAPPING SEMI-CON



**DIMENSION CUTBACK TO CUTBACK = 20 ½"**

**SPECIFICATION: NOT BE GREATER THAN 19 ¾"**






**DIMENSION CUTBACK TO CUTBACK = 20 ½"**  
**SPECIFICATION - NOT BE GREATER THAN 19 ¾"**



**Right side semi-con cutback is non-radial and would likely exhibit substandard performance.**





**SPLICE BODY NOT OVERLAPPING SEMI-CON**



**SPLICE BODY NOT OVERLAPPING SEMI-CON; INSULATION IS VISIBLE**





**BLUE DISCHARGE CONTROL COMPOUND (DCC) SCARCE ALONG INSULATION**

**SPECIFICATION: APPLY DCC ABUNDANTLY ALONG INSULATION AND SEMI-CON CUTBACK**



**IMPROPER CUTBACKS**





**SPLICE BODY NOT OVERLAPPING SEMI-CON**



# Lessons Learned

- Importance of understanding the ultimate build out of customer sites
- Found value in spending money upfront to perform extensive commissioning testing especially on key account customers who have sensitive loads.
- This whole ordeal showed the APS team (engineering, maintenance crews, contractors) the importance of challenging each other respectfully and embracing different perspectives.
- Precise workmanship is essential to ensure the safety, reliability and longevity of feeders.