



FPL URD Commissioning Experience

Clark Williams

Principal Engineer

10/21/2024

Agenda

- FPL Overview
- Background and Initial Steps
- Pilot Implementation Decisions
- What is SSUP?
- Pilot Objectives
- Testing Findings and Preventative Actions
- Final Thoughts and Recommendations



FPL is part of a larger company and consists of multiple, main divisions

Florida Power & Light – An Overview

- **Investor-owned, regulated utility under NextEra Energy umbrella**
- **Power Generation and Power Delivery divisions within FPL**
 - Power Delivery includes substation, transmission, and distribution
 - Power Generation includes nuclear, solar groups
- **Approximately 8,700 employees**
 - 34% IBEW bargaining unit



Success on starting with the technology then moving on to the dollars

Background and Initial Steps

- **Management buy-in on technology effectiveness**
 - Explanation of partial discharge technology
 - Comparison of offline PD versus DC hi-pot, VLF, tan delta, and online PD
- **Further discussions on reliability and cost**
 - Reliability: reduce future outages due to workmanship or defects
 - Cost: Reduce future O&M spend by capital spend now

FPL loves piloting new ideas to see if they will fit in with our current processes

Pilot Implementation Decisions

- How many sections is enough for statistical significance?
- What group within FPL should do the pilot?
- How many contractors should be tested?
- What does the testing process look like with the contractors?



FPL has been hardening our distribution (and transmission) grid since 2006

SSUP – Storm Secure Underground Program

- Continuation of FPL hardening program
 - Started with OH feeder wood to concrete pole upgrades
- Undergrounding poor-performing laterals, mostly rear-lot
 - Moving OH rear-of to UG front yard
 - Improved reliability and crew access
 - Vegetation O&M reduction
 - Faster storm response
 - HDD to reduce customer impact



SSUP is the division where the IMCORP pilot took place

New cable on 3 SSUP projects in PBC selected for IMCORP testing prior to energization

Pilot Objectives


1. Root causes and defect rate
2. Proactive testing vs reactive restoration



New cable on 3 SSUP projects in PBC selected for IMCORP testing prior to energization

Pilot Objectives


1. Defect rate and root causes
2. Proactive testing vs reactive restoration



14.2% defect rate caused by workmanship failures

Testing Findings

- **119 new cable segments tested**
 - 6 segments short-term failure¹ risks → 5.0%
 - 11 segments long-term failure² risks → 9.2%
 - 1 outlier failure (cable cut)
- **Failure modes → 100% workmanship**
 - Non-square cuts
 - Inadequate use of void filler
- **Costs**
 - \$166k total → \$1,395/segment
 - 81% IMCORP daily rate, 4% IMCORP mob fee, 15% crewmen standby rate



1) Short-term failure: >5pC at or below normal operating voltage

2) Long-term failure: >5pC above normal operating voltage, assumed failure prior to 40-year life

Implementing preventative actions will reduce defect rate

New Cable Installation - Preventative Actions

- Well maintained semicon scoring tools
- Semicon layer is cut square
- Adequate use of void filler
- Contamination control on dirt roads



Dull semi-con scoring tool



Implementing preventative actions and targeted quality check testing will reduce defect rate

Thoughts and Recommendations

- **The technology works! Workmanship issues were found and mitigated**
- **Production and cost improvements on expanded program**
- **For the future: limited, annual spot testing of vendors/regions**
 - Realize base savings
 - Contractors have “skin in the game”
 - Implementation of monetary penalty if high defect rate
 - Limit opportunity costs
 - Money spent on SSUP projects versus testing
 - Training of incoming apprentices so workmanship mistakes are quickly ameliorated

QUESTIONS

